



**Southern Connecticut  
State University**

Office of Facilities Operations and Planning  
615 Fitch Street  
Hamden, CT 06514-4803  
Tel: (203)392-6051  
Fax: (203)392-6058

**Facilities Planning Department** 615 Fitch Street, Hamden, CT 06514 Tel (203)392-6055 Fax (203)392-6058

**Connecticut Hall lighting Replacement - 2023**

**Project Number: SCSU-2023-03**

**Bid No.: RFQ-23-SCSU-03**

**ADDENDUM NO. 1**

**March 23, 2023**

TO: Prospective Contractors of Record

FROM: Peter J. Visentin, Director of Architectural Services  
Richard L. Glasson, Purchasing Assistant  
Procurement, Southern Connecticut State University 501 Crescent Street, New Haven, CT 06515-1355  
Tel 203-392-6702

REFERENCE: Proposal Documents For:  
Connecticut Hall Lighting Replacement - 2023  
Project Number: SCSU-2023-03  
Bid No.: RFQ-23-SCSU-03

This Addendum forms a part of the contract documents and modifies the original proposal documents, Dated March 8, 2023.

**Item 1 CLARIFICATION –PROJECT MANUAL FOR BIDDERS:**

The University has very strict requirements that a contractor must have the experience and capability to do the work.

The Owner will consider requests for equals or substitutions if made prior to the Receipt of the Competitive Bid. The information on all materials shall be consistent with the information in the specifications.

**Item 2 ADDITIONAL INFORMATION:**

Electrical Permit is not required for this project.

The University will be working with OSBI, and OSBI will be doing inspections. General Contractor will need to contact OSBI for their list of required inspections and notifications requirements.

For insurance requirements, see Certificate of Insurance, 4 pages, in Project Manual.

The project is tax exempt.

Where new ¾" conduits are installed and visible, they should NOT be painted.

Lift size should be compatible with floor slab: 5" concrete slab, live load 100 lbs/sq ft.  
Lift can be stored on work floor with nearby receptacles as designated by owner.

**Connecticut Hall Lighting Replacement -2023**  
**Project Number: SCSU-2023-03**

***Bid No.: RFQ-23-SCSU-03***

**ADDENDUM NO. 1**  
**March 23, 2023**

**Item 3 ELECTRICAL QUESTIONS:**

1. *New Work – Existing Panel B is recessed into a concrete wall, New time clock and contactor will need to be surface mounted.*  
New contactor and time clock may be surface mounted.
2. *Are the existing lighting circuits to be discontinued being removed from the physical breakers in the supplied panels?*  
All abandoned circuits are to be removed back to the circuit breaker.
3. *Are there ground wires currently installed at the existing fixtures?*  
No ground wires are installed at the existing fixtures.

**ATTACHMENTS:**

**CONTRACTOR SHALL ACKNOWLEDGE RECEIPT OF THIS  
ADDENDUM ON THE BID FORM**

**END OF ADDENDUM NO. 1**

Sincerely yours,

*Peter J. Visentin*

Peter J. Visentin, AIA  
Director of Architectural Services

*Richard L. Glasson*

Richard L. Glasson  
Purchasing Assistant